

Solid Waste Division

Wendy Thompson McNatt Recycling Coordinator wmcnatt@greenvillecounty.org (864) 243-9672 www.greenvillecounty.org

FY25 Solid Waste Creativity with Waste Reduction Grant Application

1. Local Government Name: County of Greenville Solid Waste Division

### 2. Key Contacts:

Project Manager: Marcia Papin, Director of Solid Waste 11075 Augusta Road, Honea Path, SC 29654 Phone: 864-243-9672 Fax: 864-243-5210 Email: <u>mpapin@greenvillecounty.org</u>

Finance Director: Ruth Parris, Budget Director 301 University Ridge, Suite N-2400, Greenville, SC 29601 Phone: 864-467-7037 Fax: 864-467-7340 Email: <u>rparris@greenvillecounty.org</u>

Authorized Representative: Joseph Kernell, County Administrator 301 University Ridge, Suite N-4000, Greenville, SC 29601 Phone: 864-467-7105 Fax: 864-467-7151 Email: jkernell@greenvillecounty.org

# 3. Overall Project Description:

Greenville County (GC) seeks to revive its composting facility following the closure of Atlas Organics, its former partner. The project involves amending the permit, refurbishing the facility, acquiring equipment like a trommel screen, and recommencing composting operations to cater to food waste collectors and generators in the Upstate region.

#### 4. Items for Grant Funding:

Grant funds will be allocated towards purchasing a trommel screen for compost operations.

#### 5. Target Audience and Communication Strategy:

Target audience includes curbside and commercial collectors, residents who separate organic waste, gardeners, and farmers. Communication will utilize GC's Solid Waste Website, signage at waste centers, and distribution of brochures.

#### 6. Projected Timeline:

The project is in the planning stage. Permit amendments and equipment assessment are underway. Once approved, installation and testing will follow.

#### 7. Community Partners and Support:

Partners like Smart Recycling, Landscapers Supply, Betterearth, and Republic Services have provided letters of support.

#### 8. Community Benefits and Program Efficiency:

The project will establish a Public Sector Organics Collection and Composting Facility, initially producing 4,000 tons of STA Certified compost annually, promoting waste diversion and public participation.

#### 9. Utilization of Existing Infrastructure:

The project will repurpose the site formerly operated by Atlas Organics, leveraging existing infrastructure.

#### 10. Sustainability Beyond the Grant:

After grant completion, operations will continue with County staff, support from identified partners and the public. Revenues through tipping fees and compost sales will provide the funding for the program.


#### 11. Regional Impact:

The facility will serve the Upstate Region, promoting organic recycling drop-off locations, opportunities for industrial and commercial generators.

#### 12. Regional Application Breakdown:

Not applicable.

13. Budget:
DZT621 Series Trommel:
Trommel: \$455,000.00 (plus tax, shipping, and extended warranty)
TOTAL AMOUNT REQUESTED \$100,00.00



# **SPECIFICATIONS**

#### **DIAMOND Z DZT621 TROMMEL**

#### **POWER SYSTEMS and STRUCTURE**

- CAT® 110 HP (82kw) Tier IV Final diesel engine
- 80 gallon (302L) fuel tank allows 16+ hours of continuous run-time
- 125 gallon (473L) hydraulic tank with cooler Tracked undercarriage with 16"
- (400mm) shoe width Centralized lubrication — 1 central grease
- bank for the entire machine!

#### TROMMEL SCREEN

- 6' x 21' (1.8m x 6.4m) trommel drum 340 Sq. Feet (31.6 Sq. Meters) of actual screen cloth
- Cable/hinge lock design (Rapid Change System) allows quick screen replacement. No additional drum purchase required
- 4 self-cleaning brushes, adjustable from the ground, maintain efficient performance
- · Screens included are standard wire cloth 3/8" - 2" (10mm - 50mm)
- · Heavy-duty steel drum shell with large triangular tumbling paddles • Four-wheel trommel drum drive
- · Barrel angle adjustable from 0-6°

#### **CONVEYOR/BELTS**

- · Cleated overs belt is 42" (1,067mm) wide, 220 PIW
- · Cleated stacker/fines belt is 42" (1,067mm) wide, 220 PIW

Diamond Z

- · Unders belt is 48" (1,220mm) wide
- · Feeder belt is 42" (1,067mm) wide
- · Spring-loaded scraper bars
- · Four guide rollers per conveyor for belt tracking
- 14'-8" (4.4m) discharge height on side conveyor allows direct truck loading

Twin Chimneys Landfill • 11075 Augusta Road • Honea Path, SC 29654 • Fax (864) 243-5276



Trommel \$455,000.00 plus tax, shipping and extended warranty.

# 14. Additional Funding:

Any shortfalls beyond grant funding will be addressed through Greenville County Solid Waste Division's capital equipment budget.